


Cantilever printer

321-94

OFFSET PRINTING MACHINE FOR:

TABLETS
CAPLETS
CAPSULES

CANDIES
SOFTGELS
GUMBALLS



DESIGNED FOR:

- Hard or soft shell gelatin *capsules*. Single or two color printing; linear, radial or radial rectified.
- Film or sugar coated *tablets or caplets*. One or two sided printing.

CAPABILITIES:

Tablets:

One sided up to 350,000/hr.
Two sided up to 150,000/hr.

Capsules:

Linear printing up to 300,000/hr.
Linear, *rectified* up to 150,000/hr.
Radial, *non-rectified* up to 150,000/hr.
Radial, *rectified* up to 120,000/hr.

OPTIONAL PARTS:

Cantilevered design allows easy and rapid changeover and the flexibility of either capsule or tablet printing using same base machine. Parts are custom designed for any size or shape product.

ACKLEY MACHINE CORPORATION

1273 North Church Street, Moorestown, New Jersey 08057
TEL. (609) 234-3626 FAX: (609) 234-8657

specifications

POWER REQUIREMENTS
SINGLE SIDE AND CAPSULES

110 volts AC with ¾ hp DC variable speed motor and controller for ease in set up and variable production output control.

AIR SUPPLY: 80 PSI @ 20 CFM continuous.
VACUUM: 30" H₂O @70 CFM—capsule models only.

DOUBLE SIDE
110 volts AC with 1 hp DC variable speed motor and controller for ease in set up and variable production output control.




AIR SUPPLY: 80 PSI @ 25 CFM continuous.
VACUUM: 75" H₂O @ 206 CFM—3½ HP 3 PHASE 230 VOLTS
OPTIONAL: Installed rotary vacuum pump.

CONSTRUCTION:
Base frame of solid aluminum. Component parts have the latest USDA coatings on all contact surfaces for hygiene and easy maintenance.

DIMENSIONS:
As installed—56½" (H) × 24" (W) × 62⅞" (L)

SHIPPING WEIGHT:
Approx. 1,100 lbs.

SAFETY FEATURES:
Micro switch interlocks on all guards and manual reset necessary after any power interruption.



ACKLEY MACHINE CORPORATION